

**Stack Test Plan
Emission Testing
Grain Handling
Emissions Units EU-02 & EU-03**

Bunge North America, Inc.
Emporia, Kansas
Source ID No. 1110008 | Construction Permit No. CSP03163

Submitted to:

Bureau of Air, Air Compliance and Enforcement
Kansas Department of Health & Environment
1000 SW Jackson Street
Topeka, KS 66612

And

Kansas Compliance Officer
Air Branch
Enforcement and Compliance Assurance Division
U.S. EPA, Region 7
11201 Renner Blvd.
Lenexa, Kansas 66219

Facility Information

Bunge North America, Inc. (Bunge) operates a soybean oil extraction facility located at 701 E 6th Avenue in Emporia, KS. The facility operates under Source ID No. 1110008. The facility is required to perform stack testing by its Air Construction Permit, No. CSP03163.

Vince Breedlove, EHS Manager, is the facility contact. Vince can be reached at Vince.Breedlove@Bunge.com or by phone at (712) 789-0947. PPE required at the facility include steel toes, hard hat, high visibility vest, and safety glasses. Hearing protection is required in some locations at the facility.

Test Company Information

Bunge is in the process of selecting a vendor to complete the performance test. One of the following test firms will conduct the performance test:

Testing Firm	Address
RWDI USA LLC	24445 Forterra Drive Warren, MI 48089
Montrose Environmental Group, Inc.	5120 Northshore Drive North Little Rock, AR 72118
Stack Test Group, LLC	1500 Boyce Memorial Drive Ottawa, IL 61350

Because the scope of the performance test is limited to visible emission observations pursuant to Method 9, no laboratory testing will be completed; therefore this notification does not include the name, address, or contact information for a laboratory.

Test Information

The testing will be completed to comply with the requirements of the following:

- Subpart DD of the New Source Performance Standards (NSPS), *Standards of Performance for Grain Elevators*;
- Subpart A of the NSPS, *General Provisions*; and,
- Construction permit No. CSP03163.

The scope of this test plan is limited to the visible emissions observations for emissions units EU-02 and EU-03, which are part of the *All Grain Handling* affected facility. These emissions units are required to perform an initial compliance test under Subpart DD.

Testing is scheduled to occur from Monday, March 31 through Friday, April 4. Testing is expected to begin each day at 7 am.

Visible emissions testing will be conducted pursuant to US EPA Method 9 for emissions units EU-02 and EU-03. Visible emissions observations will be conducted as follows:

- Observations will include at least 3, one-hour runs; and,
- Where possible, observations will be conducted concurrently, up to four (4) points at a time.

Pursuant to Subpart DD, fugitive emissions from *All Grain Handling* operations must not exhibit greater than 0 percent opacity. Bunge will demonstrate compliance with this limit using the six-minute averages from its Method 9 observations.

Emission Point Information

Not applicable to this test plan, which is for fugitive visible emission observations pursuant to Method 9 only.

Control Equipment Information

This test plan addresses fugitive visible emissions observations pursuant to Method 9. The grain handling equipment is aspirated by the following baghouses:

- EU-02 is aspirated by the CE-EDTA baghouse; and,
- EU-03 is aspirated by the CE-DKICE baghouse.

Each baghouse is rated for 17,000 cubic feet per minute with an expected efficiency of 0.00034 gr/dscf. Because the plan is for monitoring fugitive emissions, no control equipment data will be monitored during the test.

Please note that:

- No gas conditioning occurs prior to the control equipment;
- No adjustments have been made to the control equipment for the previous six months; and,
- The equipment has not undergone performance testing previously.

Process Equipment Information

Bunge operates a series of grain handling equipment, such as conveyors and legs, which transfer soybeans from the storage bins and silos at the facility to the extraction process. The actual maximum achieved capacity of the process is approximately 95,000 bushels per day. The emissions units normally operate 24 hours per day.

Bunge will monitor and record the following process data during the test to ensure representative operation:

- The level of soybeans in the dryer hopper at the start and end of each test run; and,
- The level of soybeans in the silo or bin which is having soybeans reclaimed at the start and end of each test run.

Quality Control Information

Field data sheets will consist of the Method 9 observation records, which are modeled after **Figure 9–2** in US EPA's Method 9.

No chain of custody records, calibration sheets, or analytical procedures are necessary for this test plan.

Relative Accuracy Test Audits

Not applicable to this test plan.